


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-179-00180-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 11 Twp. 8 Rge. 27 (W)
Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner C. R. A. & Aylward Drilling Company
Lease Name Davis "L" Well No. 1
Office Address 813 1st National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 10 1956
Application for plugging filed May 11 1956
Application for plugging approved May 11 1956
Plugging commenced May 11 1956
Plugging completed May 11 1956
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4000' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	363'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 4000' to 350'; Halliburton plug at 350' and 1/3 sack hulls and 15 sacks of cement mixed and dumped in surface pipe filling to 300'; mud 300' to 40'; Halliburton plug and 1/3 sack hulls with 10 sacks of cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1956
CONSERVATION DIVISION
WICHITA, KANSAS


5-24-56

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aylward Drilling Company
Address 813 First National Bank Bldg. - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Paul W. Hesse (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse
813 1st Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of May, 1956
December 11, 1957
Duane Jessup
Notary Public.



PLUGGING
FILE SEC 11 T 8 R 27W
BOOK PAGE 63 LINE 10

15-179-00180-00-00

DAVIS "L" #1

Casing Record:

8 5/8" - 363'

Company: C.R.A. & Aylward Drilling Company
Contractor: Aylward Drilling Company

Commenced: May 1, 1956
Completed: May 10, 1956

Location:

SE NEESW 11-8-27W
Sheridan County, Kansas

Elev.: 2570 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	60	Set 8 5/8" casing at 363' w/225 sacks cement
Sand	60	75	
Gyp	75	122	Geological Tops:
Sand	122	313	
Blue Shale	313	790	Anhydrite 2228
Shale	790	1090	Heebner 3716
Sand	1090	1160	Toronto 3743
Shale and shells	1160	1380	Lansing 3759
Sand	1380	1410	Base/Kan. City 3973
Shale and shells	1410	1885	R.T.D. 3999
Sand	1885	2004	
Shale and red rock	2004	2065	
Shale and red bed	2065	2237	DST 3781-3801 (20') Open 30 min., shut in
Anhydrite	2237	2262	20 min. Weak blow 4 min. - died, by-passed,
Shale and shells	2262	2540	weak blow 3 min. - died. Rec. 15' Mud.
Shale, shells and lime	2540	2715	BHP 1100#. FP 0.
Lime and shale	2715	3630	
Lime	3630	3790	
Lime and shale	3790	3802	
Lime	3802	3842	
Lime and shale	3842	3888	
Lime	3888	3955	
Lime and shale	3955	4000 T.D.	D. & A.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse
Paul W. Hesse

Subscribed and sworn to before me this 23rd day of May, 1956.



My commission expires December 11, 1957

Duane Jessup
Duane Jessup - Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1956
CONSERVATION DIVISION
Wichita, Kansas
S-24-56

PLUGGING
FILE SEC. 11 T. 8 R. 27W
BOOK PAGE 63 LINE 10