


15-179-20393-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Sheridan County, Sec. 14 Twp. 8S Rge. XX 27 (W)  
Location as "NE/CNW/SW" or footage from lines 150' E. of SE SW SE  
Lease Owner The National Oil Company  
Lease Name Taylor Well No. #1  
Office Address 200 W. Douglas, Suite 550, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 16 1974  
Application for plugging filed (verbally) October 16 1974  
Application for plugging approved (verbally) October 16 1974  
Plugging commenced October 16 1974  
Plugging completed October 16 1974  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols  
Producing formation Depth to top Bottom Total Depth of Well 3900 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st Plug set @ 1420' with 70 sacks  
2nd Plug set @ 220' with 30 sacks  
3rd Plug set @ 40' with 10 sacks

State Plugger: Bill Nichols

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1974  
CONSERVATION DIVISION  
Wichita, Kansas

10-21-74

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF Sedgwick, ss.  
Jerry A. Langrehr

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 18th day of October, 1974



Nancy E. Bledsoe  
Nancy E. Bledsoe Notary Public.

April 8, 1978

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 21 1974  
 CONSERVATION DIVISION  
 Wichita, Kansas

CONTRACTOR'S WELL LOG

15-179-20393-00-00

OPERATOR: The National Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: TAYLOR #1  
 LOCATION: 150' E of SE SW SE, Sec. 14-8S-27W  
 Sheridan County, Kansas  
 GEOLOGIST: Richard E. Roby  
 SPUD DATE: October 8, 1974  
 COMPLETION DATE: October 16, 1974

0	170	Surface Dirt & Sand
170	210	Shale
210	1310	Shale & Hard Sand
1310	1865	Sand & Shale
1865	2126	Shale & Sand
2126	2161	Anhydrite
2161	2511	Shale
2511	3030	Shale & Lime
3030	3170	Lime & Shale
3170	3385	Shale & Lime
3385	3654	Lime & Shale
3654	3900	Lime
	3900	Rotary Table Depth

Drilled 212' of 12 1/4" hole. Set 5 jts. used 8-5/8" surface casing @ 210'.  
 Cemented with 150 sacks Quick-Set cement. Plug was down @ 5:00 p.m., 10-8-74.  
 D & A: 1st Plug set @ 1420' w/70 sacks, 2nd plug set @ 220' with 30 sacks,  
 3rd plug set @ 40' w/10 sacks.

Sample Tops:		Elevation:
Anhydrite	2126 (+366)	2492' K.B.
B/Anhydrite	2161 (+331)	2490' D.F.
		2488' G.L.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the TAYLOR #1, SE SW SE, Section 14-8S-27W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr  
 Jerry A. Langrehr, Exec. Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 18th day of October, 1974.

Nancy E. Bledsoe  
 Nancy E. Bledsoe - Notary Public

