

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Sheridan County, Sec. 16 Twp. 8 Rge. 27 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. C N₂ SW SE
Lease Owner Dreiling Oil, Inc.
Lease Name Weeks Well No. 1
Office Address Rt. #2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-18 1973
Application for plugging filed 9-18 1973
Application for plugging approved 9-18 1973
Plugging commenced 9-18 1973
Plugging completed 9-18 1973
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas 67601
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,962 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	167'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug was set @ 1,325' w/110 cu. ft. cement
2nd plug was set @ 180' w/30 cu. ft. cement
3rd plug was set @ 40' w/10 cu. ft. cement

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1973
CONSERVATION DIVISION
Wichita, Kansas

9-21-73


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Dreiling Oil, Inc.
Address Rt. #2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Joe Hess, Sec. Treas. of Drlg. Contrc. (employee of owner) or (contractor or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe Hess
JOE HESS, RT. #2, Victoria, Kansas 67671
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September, 19 73

My commission expires September 13, 1976.
Cecilia Basgall
Cecilia Basgall Notary Public.



DREILING OIL, INC.

Victoria, Kansas 67671

15-179-20365-00-00

Dreiling Oil, Inc.		WELL LOG		
	Rt. #2			
Company	Victoria, Kansas 67671	Sec. 16	Twp. 8	Rng. 27
Farm	Weeks No. 1	Location	C N $\frac{1}{2}$ SW SE	
Total Depth	3,962'	County	Sheridan	
Comm.	9-8-73	Comp.	9-18-73	Elevation: 2528 K. B.
Contractor	Dreiling Oil, Inc. Rt. #2 Victoria, Kansas 67671		2525	D. F.
			2523	G. R.
		Production:	D & A	
	Casing Record	Cement Record		
	167' - 8 5/8"	125 sacks cement		

Figures Indicate Bottom of Formations

0'	70'	Top Soil
70'	167'	Shale
167'	1024'	Shale
1024'	2182'	Shale & Sand
2182'	2218'	Anhydrite
2218'	2880'	Shale
2880'	3205'	Shale & Lime
3205'	3430'	Lime & Shale
3430'	3962'	Lime
3962'	T.D.	

RECEIVED
STATE DEPARTMENT OF COMMERCE

SEP 21 1973

SECRETARY OF STATE
STATE DEPARTMENT


9-21-73

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Joe Hess, Secretary Treasurer, of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Weeks #1.

Joe Hess
JOE HESS

Subscribed and sworn to before me this 20th day of September, 1973.



Cecilia Basgall
Cecilia Basgall Notary Public

My commission expires: September 13, 1976.