


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-179-05175-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 22 Twp. 8 Rge. 27 (E) W (W)
Location as "NE/CNW/SE" or footage from lines SE SE SE
Lease Owner K & E Drilling, Inc.
Lease Name Simonton #1 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 8-6-58 19
Plugging completed 8-8-58 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Fabricius
Producing formation Depth to top Bottom Total Depth of Well 3932 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	273'	none
				7"	3930'	1392'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3932' and found it open.
Filled w/sand to 3875' and dumped 4 sacks of cement. Pulled 7" casing. Cleared hole and bailed off oil. Mudded the hole to 270', set a 10' rock bridge and ran 25 sacks of cement. Mudded the hole to 40', set a 10' rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1958

Name of Plugging Contractor West Supply Co., Inc. (If additional description is necessary, use BACK of this sheet)
Address Chase, Kansas


CON DIVISION
Kansas

STATE OF KANSAS COUNTY OF RICE
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 14th day of August, 1958

9-27-58 Thomas V. Duggin Notary Public.



PLUGGING
FILE SEC 22 T 8 R 27W
BOOK PAGE 119 LINE 4

15-179-05175-00-00

W E L L L O G

OPERATOR:	MYRON BUTTRAM 12 Northwest 10th Oklahoma City, Okla.	FARM NAME:	#1 SIMONTON
CONTRACTOR:	K & E DRILLING, INC. 719 Union Center Wichita, Kansas	LOCATION:	SE SE SE Sec. 22-86-27W Sheridan County, Kansas
CASING:	10-3/4" @ 273 (275 sx) 7" @ 3930 (125 sx)	COMMENCED:	1-31-57
R.T.D.	3930/	COMPLETED:	2-11-57
		PRODUCTION:	LABSING - OIL
		ELEVATION:	unknown

FORMATION RECORD

Depths shown indicate the bottom of formations

Clay & Sand	60
Shale	120
Sandy Shale	210
Shale	440
Shale & Shells	1715
Sand & Shale	2000
Red Bed & Shale	2165
Anhydrite	2205
Shale & Shells	2300
Lime & Shale	2485
Shale & Lime	2605
Lime & Shale	3175
Lime	3320
Shale & Lime	3639
Lime & Shale	3720
Lime	3930
R.T.D.	3930

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1959
CONSERVATION DIVISION
WICHITA
2-27-59

CERTIFICATION

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Dale Silcott of the K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the log of the #1 SIMONTON well.

Dale Silcott

Dale Silcott

Subscribed and sworn to before me this 14th day of February, 1957

Patricia M. Edwards

Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.

PLUGGING
FILE SEC. 22 T. 8 R27W
BOOK PAGE 119 LINE 4