



13-179-20064-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

208 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED
CORPORATION COMMISSION

SEP 14 1982

CONSERVATION DIVISION
Wichita, Kansas

9-14-82

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Wagner of Murfin Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Pratt Oil Operation

Complete Address: P.O. Box 370, Hays, Ks. 67601

Lease Name: Albers Well No. 1-5

Location: SE-SE-SE Sec. 5 Twp. 8 Rge. 26 (E) (W)

County: Sheridan Total Depth: 4000'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Wagner was instructed to plug the well as follows:

8 5/8" - 225' S.P. cnc. w/ 135 sacks common - 2% Gel. - 3% Cal. Cl.
Ordered 160 sacks 50% permix - 4% Gel. - 3% Cal. Cl. + 8 5/8" plug. spot w/
drill stem w/ heavy mud between all plugs. 1st plug @ 1300' w/ 100 sacks cement
2nd plug @ 250' w/ 40 sacks. 3rd plug - solid bridge of shells & plug at
40' w/ 10 sacks. Circulated 10 sacks in rat hole.

Very truly yours,

Patte R. School
Conservation Division Agent