

State of Kansas



15-179-20049-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
OCT 23 1967
10-23-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas,

Lease Name: Cass Well No. 1

Location: SE-NW Sec. 6 Twp. 8 Rge. (E)(W)26

County Sheridan Total Depth 4080' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

199'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota Section from 2090' to 1930'.

Circulate hole with heavy mud. Pull DP to 2110' and displace 100 Sx.
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. L. Nichols

Conservation Division Agent