

State of Kansas



15-179-20028-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1967
7-12-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Vaughn Thompson of Sterling Drilling Co., has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Benjamin Tepper.

Complete Address: 830 North Mission, Wichita, Kansas.

Lease Name: Twell Well No. 1

Location: S/2-SW-SW Sec. 10 Twp. 8 Rge. (E)(W) 26

County Sheridan Total Depth 3845' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

230'--7" OD Surface pipe, cement circulated with 200 Sx. (6 1/4" hole)
Top of Dakota picked from Geolograph chart from 785' to 925'.

Fill hole from 945' to 685' with 60 Sx. cement.

Set plug @ 240' and displace 15 Sx. cement thru DP.

Set plug @ 40' with 1/2 sack hulls and 10 Sx. cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent