

State of Kansas



15779-20023-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1967

7-3-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. V. L. Thompson of Sterling Drilling Co., has this

date requested permission to plug the following described well:
Joe Katz Oil a/c

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Joe Katz Oil a/c, Benjamin B. Tepper, Agent,

Complete Address: 7751 Carondelet Avenue, Clayton, Missouri.

Lease Name: Claude Bell Well No. 1

Location: CNE-SE-SW Sec. 16 Twp. 8 Rge. (E)(W) 26

County Sheridan Total Depth 3588' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

203' -- 7" OD Surface pipe, cement circulated with 150 Sx. (6 1/4" hole).

Circulate hole with heavy mud, set plug @ 600' and 15 Sx. cement.

" " 210' and 15 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

Conservation Division Agent