

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217RECEIVED
STATE CORPORATION COMMISSIONNOV 25 1974
11. 25-1974
CONSERVATION DIVISION
Wichita, KansasVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gib Scheck of Dreiling Oil, Incorporated has this
date requested permission to plug the following described well:Mr. Scheck guarantees payment of the plugging fee.Operator's full Name: Dreiling Oil, Incorporated,Complete Address: R. R. #2, Victoria, Kansas.Lease Name: Kysar Well No. 2Location: CSW/4 Sec. 17 Twp. 8 Rge. (E)(W) 26County: Sheridan Total Depth 3875' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Scheck was instructed to plug the well as follows:166'--8 5/8" Surface casing, cement circulated with 165 Sx.
3875'--4 1/2" Production casing cemented on bottom with 175 Sx. Top of per-
forations @ 3620'.Push plug to 3400', sand back to 3350' and set 4 Sx. cement with dump
bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks
gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent