



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1971

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis,

Complete Address: 4120 East 51st Street, Tulsa, Oklahoma.

Lease Name: Karnes Well No. 2

Location: App; SW-NW-SE Sec. 18 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3716' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

213'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and LO Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent