

State of Kansas



15-179-20038-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
AUG 28 1967
8-28-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Moore of C & G Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Dane G. Hansen Trust

Complete Address: Logan, Kansas

Lease Name: Taylor Well No. 1

Location: SE SE SE Sec. 19 Twp. 8 Rge. 26 (E)(W) X

County Sheridan Total Depth 3900 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1700' and displace
100 sc cement thru drill pipe. Heavy mud to 190' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug
1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc
cement.

Very truly yours,

Geo. J. Mussey
Conservation Division Agent