



15-179-20071-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1968
CONSERVATION DIVISION
Wichita, Kansas

226-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Miller of Leo J. Dreiling & Sons, Inc. has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company.

Complete Address: Victoria, Kansas.

Lease Name: McClelland Well No. B-1

Location: SW-SW-SW Sec. 21 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3870 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

138'--8 5/8" Surface pipe, cement circulated with 125 Sx.
Dakota section from 950' to 1140'.

Circulate hole with heavy mud. Pull DP to 1160' and displace 100 Sx.
cement thru DP. Pull DP to 150' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent