



15-179-20273-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 3 1970  
CONSERVATION DIVISION  
Wichita, Kansas

11-3-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg. Inc. & Consolidated Oil & Gas, Inc.,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Mizer Well No. 1

Location: CS/2-SW-SE Sec. 21 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3940' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Weber was instructed to plug the well as follows:

246'--8 5/8" Surface casing, cement circulated with 175 Sx. (6 3/4" Hole).  
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1280' and displace 50 Sx. cement thru DP. Pull DP to 270' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent