



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling Cohas this date requested permission to plug the following described well:

Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: M. J. Bove Operating Company,

Complete Address: 754 East Wichita, Russell, Kansas.

Lease Name: Pratt Well No. 9

Location: NW-NW-SE Sec. 22 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3840 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Barnes was instructed to plug the well as follows:

277'--10 3/4" Surface casing, cement circulated with 250 Sx.  
3802'--7" OD Production casing cemented with 225 Sx. (9" Hole).  
Top perforations from 3620' to 3624'.

Push plug to 3500', sand to 3490' and set 5 Sx. cement with dump bailer.  
Pull 7" casing and squeeze well with 35 sacks gel plus 5 sacks hulls and 165 Sx. cement staged.

RECEIVED  
 STATE CORPORATION COMMISSION  
 Very truly yours,

JUL 1 1968

CONSERVATION DIVISION  
 Wichita, Kansas

*H. L. Nichols*  
 Conservation Division Agent