



15-179-20144-00-00

B. DOCKING Governor
 SAFFELS Chairman
 DOTY Commissioner
 J. GREENLEAF Commissioner
 W. B. HARVEY Secretary
 LAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 2 - 1968
 CONSERVATION DIVISION
 Wichita, Kansas

102-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Vernon Zorn of L. J. Dreiling & Sons, Inc., has this
 date requested permission to plug the following described well:

Mr. Zorn guarantees payment of the plugging fee.

Operator's full Name: M. J. Bove Operating Company,

Complete Address: 754 East Wichita Avenue, Russell, Kansas.

Lease Name: Pratt Well No. 12

Location: SE-SE-NE Sec. 22 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3805 Oil Well

Gas Well Input Well sWD Well D & A X Lost-Hole

Mr. Zorn was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,


 Conservation Division Agent