

State of Kansas



15-179-20313-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1972

CONSERVATION DIVISION
Wichita, Kansas

11-3-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Buffington of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Cow Gulch Oil Co.

Complete Address: 909 17th St. Denver, Colo.

Lease Name: Pratt "A" Well No. 1

Location: C NW SE SE Sec. 22 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3855' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Buffington was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1150' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Les F. Massey
Conservation Division Agent