



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 8 1973

CONSERVATION DIVISION  
Wichita, Kansas

8-8-73

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Co., Inc., has this

date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Inc., & Bill J. Porter,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Schaffer Well No. 1

Location: CNW-SW Sec. 22 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3800' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

223'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

*W. L. Nichols*  
Conservation Division Agent