

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-179-05209-00-01

FILE NO. 35-17

LOCATION NW NE NW

SEC. 26 TWP. 8 RGE. 26 *w*

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Schlemeyer

Operator Musgrove Pet Co Address Wichita, Kans

Field _____ County Sheridan

Total Depth 3880 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 248' circulated with cement - 5 1/2" at 3884' with
175 sax cement behind, plugged back to 3750', top perforations
at 3740'.

Filled with chat to 3730', set 4 sax cement with dump bailer,
pulled 1524' 5 1/2", filled hole with mud to 240' set rock bridge
and 20 sax cement, filled with heavy mud to 30', set rock bridge
and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC. 26 TWP. 8 RGE. 26
BOOK PAGE 35 LINE 17

RE *[Signature]*
STATE CORPORATION COMMISSION
Date NOV 7 - 1950 11-5-50
CONSERVATION DIVISION
Wichita, Kansas
11-07-1950