

9

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20298-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1972
CONSERVATION DIVISION
Wichita, Kansas
01-18-1972

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas. 107665

Lease Name Pratt Well No. A-2

Location SW-NE-NE Sec. 26 Twp. 8 Rge. (E) (W)26

County Sheridan Total Depth 3900' 48.75

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 2:00 AM Day 16 Month 1 Year 11972

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 110 Cu. Ft. cement
thru DP from 1225' to 900'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 1-18-72
INV. NO. 5035-W