

KANSAS

AP STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1971
CONSERVATION DIVISION
Wichita, Kansas
12-10-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name F & M Oil Company,

Complete Address 603 Union Center, Wichita, Kansas.

Lease Name Pratt Estate Well No. 1

Location SW-SW-NW Sec. 27 Twp. 8 Rge. (E) (W)26

County Sheridan Total Depth 3860'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 11:15 AM Day 8 Month 12 Year 1971

The above well was plugged as follows:

259'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 110 Cu. Ft. cement
thru DP. Pull DP to 275' and displaced 30 Cu. Ft. cement thru DP from 275' to 200'.

Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. J. Nichols*
Well Plugging Supervisor

INVOICED

DATE 12/10/71
INV. NO. 4801-W