

*JP*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 22 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
1-22-1969

Operator's Full Name D. G. Hansen Trust,

Complete Address: Box #187, Logan, Kansas.

Lease Name Hansen Fee Well No. D-5

Location SE-SE-NW Sec. 28 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3935

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: C & G Drilling Company,

Address: 1107 Union National Bldg., Wichita, Kans. License No.     

Operation Completed: Hour 2:15 PM Day 18 Month 1 Year 1969

The Above well was plugged as follows:

201'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru  
DP from 1175' to 850'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from  
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Dickels*  
Well Plugging Supervisor

INVOICED

DATE 1/22/69  
INV. NO. 9220-W