

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Three G Oil, Incorporated,

Complete Address 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name Hannah Pratt Well No. 1

Location NE-NE-NE Sec. 28 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 4020'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated.

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:00 AM Day 18 Month 7 Year 1969

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 170 Sx.
391 1/4'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug back nor perfor-
ations indicated. Ran measuring line and found bottom @ 3870'.

Sanded well back to 3800' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks hulls and 1 1/4 sacks gel and followed with 90
sacks cement from 1050' to 750' then 12 sacks gel from 750' to 270' and followed with
30 Sx. cement, from 270' to 180' then 4 sacks gel from 180' to 30' and finally 10 Sx.
cement from 30' to 0. Maximum Pump-in pressure--350#. Final shut-in pressure--200#.

Recovered 1125' 5 1/2" casing. (Mudding and cementing operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

STATE CORPORATION COMMISSION

DATE 9/23/69

JUL 23 1969

Signed: N. L. Nichols
Well Plugging Supervisor

INV. NO. 129-W

CONSERVATION DIVISION
Wichita, Kansas

7-23-1969