

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20072-0000

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

2-26-68

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name Karnes Well No. 1

Location SW-SE Sec. 1 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 4050'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leo J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 3:15 PM Day 19 Month 2 Year 1968

The Above well was plugged as follows:

187'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
Dakota section from 1125' to 1300'.

Circulated hole with heavy mud. Pulled DP to 1335' and displaced 100 Sx. cement thru  
DP from 1335' to 1010'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from  
210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dichek  
Well Plugging Supervisor

DATE 2/26/68  
INV. NO. 1321-W