

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20262-0000

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated.

Complete Address 370 West Wichita, Russell, Kansas.

Lease Name Haffner Well No. 1

Location CSW-SW Sec. 3 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 4045'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 1:30 PM Day 20 Month 8 Year 1970

The above well was plugged as follows:

216'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 100 Sx. cement thru  
DP from 1400' to 1075'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from  
245' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1970

DATE 8/24/70

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 2431-W

8-24-70