

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20372-00-00

RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1974

CONSERVATION DIVISION
Wichita, Kansas

2-11-74

Operator's Full Name National Oil Company,

Complete Address 550 O. W. Garvey Building, Wichita, Kansas.

Lease Name James Well No. 1

Location CNE-NE Sec. 9 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 1075'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 4:30 PM Day 7 Month 2 Year 1974

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1175'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 110 Cu. Ft. cement
thru DP from 1400' to 1075'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. P. Pichler
Well Plugging Supervisor

INVOICED

DATE 2/12/74

INV. NO. 8557-W