

4
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20077-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1968
CONSERVATION DIVISION
Wichita, Kansas

3-12-68

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name C & G Drilling Company,

Complete Address: 1107 Union National Building, Wichita, Kansas.

Lease Name Taylor Well No. 1

Location SE-SE-SW Sec. 13 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 3960'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 1:30 PM Day 6 Month 3 Year 1968

The Above well was plugged as follows:

240'--8 5/8" Surface pipe, cement circulated with 165 Sx.

Dakota section from 725' to 925'.

Circulated hole with heavy mud. Pulled DP to 960' and displaced 100 Sx. cement thru DP

from 960' to 640'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from 245' to

185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of

cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. A. Fitch
Well Plugging Supervisor

INVOICED

DATE 3/12/68

INV. NO. 7403-W