

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1972

CONSERVATION DIVISION
Wichita, Kansas

12-13-72

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20338-00-00

Operator's Full Name Amarex, Incorporated,

Complete Address Suite #200, 200 N Harvey, Oklahoma City, Oklahoma. 73102

Lease Name Orville Taylor Well No. 1

Location CSW-NE Sec. 13 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 3932'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 2:30 PM Day 11 Month 12 Year 1972

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1015'.

Circulated hole with heavy mud. Pull DP to 1240' and displaced 110 Cu. Ft. cement
thru DP from 1240' to 915'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cy. Ft.
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/13/72

INV. NO. 6922-W