

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20343-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1973
CONSERVATION DIVISION
Wichita, Kansas
5-21-73

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name O. Taylor Well No. B-2

Location SW-SE Sec. 14 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 4130'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 10:15 PM Day 18 Month 5 Year 1973

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated with 165 Sx.
3910'--4 1/2" Production casing cemented on bottom with top of cement @ 3510'. Top per-
forations from 3662' to 3664'.

Pushed plug to 3600', sanded back to 3550' and set 4 Sx. cement with dump bailer.

Pulled 4 1/2" casing (3220') and squeezed well initially with 10 sacks hulls and 12
sacks gel and followed with 110 Cu. Ft. cement from 1250' to 925' then 15 sacks gel
from 925' to 225' and followed with 30 Cu. Ft. cement from 225' to 150' then 3 sacks
gel from 150' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar.

Maximum pump-in pressure-400#. FSIP-100#. (Mudding & Cementing by Allied Cementing, Inc).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/22/73

INV. NO. 7391-W