

15-179-20356-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 5 1973

CONSERVATION DIVISION  
Wichita, Kansas

7-5-73

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Kenneth Dole and Ed. Dreiling,

Complete Address Box #262, Russell, Kansas.

Lease Name Davis Well No. 1

Location SW-SW-NE Sec. 14 Twp. 8 Rge. (E) (W)27

County Sheridan Total Depth 3915'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Russell, Kansas. License No.     

Operation Completed: Hour 3:00 AM Day 2 Month 7 Year 1973

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement  
thru DP from 1250' to 925'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: K. L. Doherty  
Well Plugging Supervisor

INVOICED

DATE 7/6/73  
INV. NO. 7600-u