

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-179-20393-00-00

RECEIVED  
OCT 21 1974  
CONSERVATION DIVISION  
Wichita, Kansas

10-21-74

Operator's Full Name National Oil Company and Amarex, Incorporated,

Complete Address Suite 550, 200 West Douglas, Wichita, Kansas.

Lease Name Taylor Well No. 1

Location 150' SE of CSE-SW-SE Sec. 11 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 3900'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.     

Operation Completed: Hour 10:00 PM Day 16 Month 10 Year 1974

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement  
thru DP from 1275' to 950'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. Dehala  
Well Plugging Supervisor

INVOICED

DATE 10/23/74  
INV. NO. 169-W