

2

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-179-20365-00-00

RECEIVED  
STATE CORPORATION COMMISSION

SEP 20 1973  
9-20-73  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name \_\_\_\_\_ Weeks \_\_\_\_\_ Well No. 1

Location CN/2-SW-SE Sec. 16 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 3962'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Above

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 2:45 AM Day 9/18 Month 9 Year 1973

The above well was plugged as follows:

166'--8 5/8" Surface casing, cement circulated with 125 Sx.  
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 110 Cu. Ft. cement  
thru DP from 1325' to 1000'. Pulled DP to 180' and displaced 30 Cu. Ft. cement thru  
DP from 180' to 105'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement from 40' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 9-20-73

INV. NO. 7941-W