

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20048-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
OCT 23 1967
10-23-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Nadel & Gussman,

Complete Address 625 Union Center, Wichita, Kansas.

Lease Name Jamison Well No. 1

Location CNE-SW Sec. 20 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 4125

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No. _____

Operation Completed: Hour 2:30PM Day 20 Month 10 Year 1967

The above well was plugged as follows:

231'--8 5/8" Surface pipe, cement circulated with 160 Sx.
Dakota section from 1200' to 1050'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement
thru DP from 1225' to 900'. Pulled DP to 240' and displaced 20 Sx. cement thru DP
from 240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dehler
Well Plugging Supervisor

DATE 10/23/67
INV. NO. 6557-11