

KANSAS

Form CP-3  
Rev. 6-9-67

*J*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-179-20091-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 31 1967  
10-31-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address Box #797, Great Bend, Kansas.

Lease Name Taylor Well No. 1

Location CSE-NE Sec. 24 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 3980'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Above

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 4:15PM Day 23 Month 10 Year 1967

The above well was plugged as follows:

201'--8 5/8" Surface pipe, cement circulated.  
Dakota section from 1025' to 850'.

Circulated hole with heavy mud, pulled DP to 1050' and displaced 100 Sx. cement thru  
DP. Pulled DP to 210' and displaced 20 Sx. cement thru DP. Pulled DP, set bridge @  
40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. L. Nichols*  
Well Plugging Supervisor

DATE 10/31/67  
INV. NO. 6590-4