



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

January 8, 1961

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date January 8, 1961, authorized the following plugging operation:

Operator's Full Name: National Drilling Co., Inc.

Complete Address: 535 Petroleum Bldg., Wichita, Kansas

Lease Name: Schneider Well No. 1

Location: C SW NW Sec. 20 Twp. 9 Rge. 9 (E) (W) X

County: Mitchell Total Depth: 4126'

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 190' with heavy mud.
Push plug and 1/2 sack hulls to 190' and cement with 20 sacks thru
drill pipe. Fill hole to 35' with heavy mud. Push plug and 1/2 sack
hulls to 35' and cement with 10 sacks. Fill, bridge, and cement
rathole with 2 sacks.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 26 1961 126-61

CONSERVATION DIVISION
 Wichita, Kansas

Very truly yours,

Signed: [Signature]
 Conservation Division Agent