



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

July 29, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-141-20107-00-00

Dear Sir:

Mr. John Collins of Revelin Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Graham-Michaelis Corporation

Complete Address: Box 274, Wichita, Kansas

Lease Name: Hachmeister Well No. 1-31

Location: 430' FNL 1550' FNL SW Sec. 31 Twp. 9 Rge. 15 (E) (W)

County: Osborne Total Depth: 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Collins was instructed to plug the well as follows:

8 3/8" - 260' - 175 sacks Quickset Elev. 2015 KB Anhydrite 1209'-50'
Circulate hole and fill with mud. Pump 50 sacks cement through
drill pipe at 800'. Pump 50 sacks cement through drill pipe
at 310'. Fill hole with mud to 40'. Push plug and 1/2 sack
hulls to 40' and cap hole with 10 sacks cement. Cement rat hole
with 10 sacks cement.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION
08-03-1981
AUG - 3 1981

Phillip R. Dick
CONSERVATION DIVISION
Wichita, Kansas
Conservation Division Agent