



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

15-141-20095-00-00

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Collins of Revin Drlg., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Reif Oil Operations

Complete Address: 614 N. Eln, Hoisington, Kansas

Lease Name: Ward "A" Well No. 1

Location: SW NE SW Sec. 35 Twp. 9S Rge. 15 XX (W)

County: Osborne Total Depth: 3586'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XX

Other well as hereafter indicated: \_\_\_\_\_

Mr. Collins was instructed to plug the well as follows:

Fill hole with mud and spot 60 sx cement at 620'.

Fill hole with mud and spot 30 sx cement at 330'.

Fill hole with mud to 40' & 1/2 sx hulls, plug, & 10 sx cem.

Fill rat hole with cement.

314' of 8 5/8" surface casing cement circ.

Very truly yours,

Duan Z Rankin  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

MAY 18 1981  
05-18-1981  
CONSERVATION DIVISION  
Wichita, Kansas