

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Prospect Oil & Gas Inc *COOP*  
Address: PO Box 837, Russell, KS 67665  
Phone: (785) 483-6266 Operator License #: 6627  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Case Morris (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-167-23474-00-00  
Lease Name: Hough-Mudd  
Well Number: 1 *KCC PKT per CP213*  
Spot Location (QQQQ): SE - SW - SE  
175 Feet from  North /  South Section Line  
1910 Feet from  East /  West Section Line  
Sec. 21 Twp. 14 S. R. 15  East  West  
County: Russell  
Date Well Completed: 11-20-07  
Plugging Commenced: 4-28-08  
Plugging Completed: 4-29-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	221	
				4 1/2	3318	2470

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dug cellar, unpacked casing head, cut nipple out of 4 1/2" collar, set floor, pulled slips, checked hole, sand was at 3030', bailed 4 sacks cement, ripped casing at 2610', worked pipe, ripped casing at 2470', pipe came free, pulled casing up to 1600', pumped 100 sacks, 300# hulls, pipe hung up, worked pipe free, pulled casing up to 840', pumped 25 sacks, 100# hulls, pulled to 450', pumped 30 sacks, 100# hulls, pulled to 250', circulated with 70 sacks to surface, pulled rest of casing.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 190 US Highway 56, Ellinwood, KS 67526  
Name of Party Responsible for Plugging Fees: Prospect Oil & Gas Inc  
State of Kansas County, Russell, ss.

PROSPECT OIL & GAS INC. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says that I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY PUBLIC  
STATE OF KANSAS  
My App. Exp. 10-13-2010

(Signature) [Signature]  
(Address) Box 837, RUSSELL, KANSAS 67665

RECEIVED  
KANSAS CORPORATION COMMISSION SUBSCRIBED and SWORN TO before me this 14 day of May, 2008  
Doni R. Haberer My Commission Expires: 10-13-2010  
Notary Public

CONSERVATION DIVISION  
WICHITA, KS

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202