

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: RAYMOND OIL COMPANY, INC.
Address: P.O. BOX 48788, WICHITA, KS 67201
Phone: (316) 267-4214 Operator License #: 5046
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5/31/08 (Date)
by: JERRY STAPLETON (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No

API Number: 15 - 101-22097-0000
Lease Name: FENLEY 'A'
Well Number: 1
Spot Location (QQQQ): NW - NE - SW - NW
1473 Feet from North / South Section Line
872 Feet from East / West Section Line
Sec. 20 Twp. 18 S. R. 27 East West
County: LANE
Date Well Completed: _____

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Plugging Commenced: 5/31/08
Plugging Completed: 5/31/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	249'	8 5/8"	241.12'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


1st Plug @ 2130' w/ 50 sx., 2nd Plug @ 1290' w/ 80 sx., 3rd Plug @ 630' w/ 50 sx.,
4th Plug @ 270' w/ 40 sx., 5th Plug @ 60' w/ 20 sx., 6th Plug @ Rathole w/ 15 sx.
Total 255 sx. of 60/40 Pozmix, 4% Gel, 1/4# Floseal per sx
By Allied Cementing, Plug Down @ 4:30 P.M. 05/31/08

Name of Plugging Contractor: L.D. DRILLING, INC. License #: 6039
Address: 7 SW 26 AVE, GREAT BEND, KS 67530

Name of Party Responsible for Plugging Fees: RAYMOND OIL COMPANY, INC.
State of KANSAS County, BARTON, ss.

SUSAN SCHNEWEIS (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 7 SW 26 AVE., GREAT BEND, KANSAS 67530



SUBSCRIBED and SWORN TO before me this 2 day of JUNE, 2008
[Signature] My Commission Expires: 2/02/11
Notary Public Rashell Patten

RECEIVED
KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 JUN 03 2008

CONSERVATION DIVISION
WICHITA, KS