

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc
Address: PO Box 2528 Liberal KS 67905
Phone: 620 629 4200 Operator License #: 5447
Type of Well: ENHR Docket #: E-12571
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 3-20-08 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 4822 Bottom: 4884 T.D. 5210'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129-10334-00-01
Lease Name: Wilburton Morrow Sand Unit
Well Number: 1102 W
Spot Location (QQQQ): _____ - _____ - NW-NW
660 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 33 Twp. 34 S. R. 41 East West
County: Morton original
Date Well Completed: 6-9-01 spud
Plugging Commenced: 3-20-08
Plugging Completed: 3-26-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1439	—
				4 1/2	5054	—

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Press. test 4 1/2 to 1500 ft @ 500 PSI. HLS set CIBP from 4590 to 4570. 4 1/2 was stuck @ 700. IPS ran CBL. Ran 2 3/8 to 1470. Mixed 25 sx plug 1470 to 1145. Pull to 600. Mixed 47 sx 600 to 0. Pull 2 3/8. Top off 4 1/2 w/45 sx. Mixed 34 sx down annulus from 136 to 0. Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: RT. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS. 67905
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) Kenny Andrews
(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED and SWORN TO before me this 28 day of May, 2008
Anita Peterson My Commission Expires: Oct 1, 2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED
MAY 30 2008
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KS

[Handwritten initials]