

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

		X	

Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Paul Turpin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2916 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2356.40

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 5 foot rock bridge at 2850 feet, dumped 5 sacks cement with bailer, set 20 foot rock bridge at 200 feet, dumped 20 sacks cement. Mud hole to 45 feet, set 5 foot rock bridge Dumped 8 sacks cement. Mud to surface.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 4 1963  
1-4-63

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kent Well Servicing Co., Inc.  
Address Box 470, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Mary Payne

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of January

My commission expires June 18, 1963

Estelene C. Phelps



Raymond Oil Company, Inc. - Lygrisse #1  
NW NW SE, 12-26S-2E  
Sedgwick County, Kansas  
Development Well

Elevation: 1375 KB  
1373 DF  
1370 GL

Contractor: Company Tools - Rig #1  
Commenced: 10/10/59  
Completed: 10/26/59 (Rotary)

Casing Record  
8-5/8" @ 169' w/150 sacks  
5-1/2" @ 2898' w/75 sacks

Figures Indicate bottom of formation

<u>Formation</u>	<u>Depth</u>
Shale	60
Lime	475
Sand	495
Shale & Red Bed	515
Lime w/shale	595
Shale & Lime	1560
Lime & Shale	2225
Lime	2280
Lime & Shale	2415
Lime	2560
Lime & Shale	2745
Lime	2831
Chert	2864
Chat, some dolomite	2874
Chat	2916
Rotary Total Depth	2916

RECEIVED  
STATE CORPORATION COMMISSION

DEC 26 1962

CONSERVATION DIVISION  
Wichita, Kansas

Tops:


Lansing	2180
Kansas City	2394
Base Kansas City	2561
Mississippian	2831
Mississippi Chat	2859
"Pay Zone"	2901

STATE OF KANSAS       )  
                                  )   SS  
COUNTY OF SEDGWICK )

I hereby certify that the above is true and correct to the best of my knowledge.

Rick P. Clinton  
Rick P. Clinton

Subscribed and sworn to before me this 29th day of October, 1959.



Mary Ellen Sampson  
Notary Public

My Commission Expires: May 13, 1962