


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sedgwick County. Sec. 12 Twp. 26 Rge. 2 (E) (W)
Location as "NE/CNW/SW" or footage from lines. C NE SW
Lease Owner Se Ro Bee Drlg. Co., Inc.
Lease Name Lygrisse Well No. 1
Office Address 5301 N. Broadway Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 7-29-65 19
Application for plugging filed 9-9-66 19
Application for plugging approved 9-12-66 19
Plugging commenced 9-16-66 19
Plugging completed 9-17-66 19
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation Depth to top Bottom Total Depth of Well 2885 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200'	none
				5 1/2	2884	2415'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with sand from 2885 to 2880' and dump 5 sacks of cement

Set 15' rock bridge from 180' to 165' and dump 20 sacks of cement

Mud hole to 40' and rock to 35', dump 10 sacks of cement to surface

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1966

9-26-66

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Flint Engineering and Construction Co.
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Ronald R. Hansen*

(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of September, 19 66

My commission expires Sept. 27, 1967

Notary Public.

59

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **SeRoBee Drilling Co., Inc.**
FARM **Lygrisse** NO. **1**


SEC. **12** T. **26** R. **2E**
LOC. **C NE SW**

TOTAL DEPTH **2385**
COMM. **7-21-65**

COMP. **7-29-65**

COUNTY **Sedgwick**
KANSAS

SHOT OR TREATED
CONTRACTOR **SeRoBee Drilling Co., Inc.**
ISSUED



CASING

20 10
15 8 **5/8 @ 200' W/150 sax**
12 6
13 5 **1/2 @ 2884 W/75 sax**

ELEVATION **1361 KB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 15	Sandy Soil
15 - 2405	Lime & Shale
2405 - 2763	Lime
2763 - 2819	Lime & Shale
2819 - 2860	Lime
2860 - 2885	Cherty Lime

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1965

CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and ~~and~~ correct copy
of the driller's log and the geological tops to the best
of my knowledge and belief.

SEROBEE DRILLING CO., INC.

By: **Paul S. Septer, President**