

STATE OF KANSAS
STATE CORPORATION COMMISSION

69

OCT 3

1967

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sedgwick County, Sec. 12 Twp. 26 Rge. 2 (E) X (XX)
Location as "NE/CNW/SW" or footage from line. 5/8 N 1/2 SW NW
Lease Owner Clinton Oil Company
Lease Name DeMoss B ANB YCC Well No. 7-3
Office Address 6810 West Highway US 51 Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed September 30 1958
Application for plugging filed September 5 1967
Application for plugging approved September 5 1967
Plugging commenced 9-18-67 1967
Plugging completed 9-21-67 1967
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production September 9 1967
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well H. Scott
Producing formation Mississippi Depth to top 2814' Bottom 2828' Total Depth of Well 2868' Feet
Show depth and thickness of all water, oil and gas formations. Plug back T.D. 2844'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	DATE	FROM	TO	SIZE	PUT IN	PULLED OUT
					8 5/8	167	None
					5 1/2	None	2431

SEP 26 1967
9-26-67
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in unit.
Cleaned out cellar. Sanded to 2800'. Dumped 5 sacks of cement.
Pulled off collar - welding on 5 1/2" collar. Working pipe.
Loaded hole with water. Working pipe. Shot pipe at 2400' and 2320'.
Pulling pipe.
Pulling pipe. Plugging well. Bailed to 180' rock bridge. Dumped 25 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

RECEIVED
OCT 5 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 25 day of September 1967

NOTARY PUBLIC
My commission expires May 27, 1969

Notary Public.

Francis M. Raymond & Warren Winne
 #3 DeMoss "B"
 495' EWL & 330'SNL N/2 S/2 NW/4, 12-26S-2E
 (approx. CN/2 SW NW/4)
 Sedgwick County, Kansas

Contractor: Raymond Oil Co., Inc.
 Elevation: 1335 KB
 RTD 2852'

Commenced: 9/9/58
 Completed: 9/15/58 (Rotary)

Casing Record:
 8-5/8" @ 167' w/150 sacks
 5-1/2 @ 2849' w/50 sacks

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Surface Clay	40
Shale & Lime	167
Lime & Shale	580
Shale & Shells	1200
Shale & Lime	2150
Lime	2215
Shale & Lime	2352
Lime	2518
Shale & Lime	2821
Chert	2852

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 5 1967
 CONSERVATION DIVISION
 Wichita, Kansas

Tops:

Lansing	2140
Kansas City	2352
Base of Kansas City	2518
Conglomerate Chert Zone	2778
Mississippi	2805
1st "Pay Zone"	2812
Mississippi Chat (2nd Pay Zone)	2849
Rotary Total Depth	2852

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that the above information is true and correct to the best of my knowledge.

Lloyd M. Greenstreet
 Lloyd M. Greenstreet

Subscribed and sworn to before me this 23rd day of September, 1958

Betty Baker
 Notary Public

My Commission Expires:

2/24/60