


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plat

Sedgwick County. Sec. 12 Twp. 26 Rge. 2c E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_

Lease Owner CE 1/2 SW NW  
Lease Name Walnut Valley Oil Well No. 2

Office Address 150 S. Rock Rd. Wichita, KS 67207  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_

oil  
Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 3-17- \_\_\_\_\_ 1987  
Plugging completed 7-26- \_\_\_\_\_ 1987  
Reason for abandonment of well or producing formation \_\_\_\_\_

dry  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3161  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>4x2</u>		<u>2,008.10</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Push plug to bottom & sand screen to 3150 and made a foot of fifteen foot rock bridge and put in 4 sack of cement. Mudded hole to 330 and made a 15 foot rock bridge and fell with 4 yards of ready mix.

MAR 30 1987  
3-30-87  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor H & H Logging Pulling

STATE OF Kansas COUNTY OF Armo, ss.  
Madeline Hurst (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Madeline Hurst  
101 E 7th Ave S Hutchinson, KS 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of 3, 1987

My commission expires \_\_\_\_\_



Madeline Hurst  
Notary Public.



# BRADEN PETROLEUM COMPANY

207 ELM

P. O. BOX 282

BURDEN, KANSAS 67019

NOVEMBER 19, 1980

WALNUT VALLEY OIL, INC.  
WICHITA, KANSAS 67207

RE: DEMOSS #2

## FORMATIONS OF INTEREST (cont.)

HUNTON LIME 3157 to 3161

BROWN DOLOMITIC LIME WITH GOOD ODOR AND SHOWS OF  
FREE OIL IN 50% OF THE SAMPLE.

THE HUNTON LIME WAS COMPARABLE TO THE #. 1 DEMOSS;  
4 1/2 INCH CASING WAS RUN TO FURTHER TEST THIS ZONE.  
CASING WAS SET 3 FEET OFF BOTTOM AND CEMENTED WITH  
100 SACKS OF CEMENT.

YOURS TRULY,

ROBERT L. BRADEN

RECEIVED  
CORPORATION COMMISSION

MAR - 9 1981

CONSERVATION DIVISION  
Wichita, Kansas

RLB/s1b

## BRADEN PETROLEUM COMPANY



207 ELM

P. O. BOX 282

BURDEN, KANSAS 67019

NOVEMBER 19, 1980

WALNUT VALLEY OIL, INC.  
150 SOUTH ROCK ROAD  
WICHITA, KANSAS 67207

RE: DEMOSS #2

CE  $\frac{1}{2}$ -SW-NW

12-26-2E

SEDGWICK COUNTY, KANSAS

DEAR SIR:

SAMPLES WERE TAKEN AND EXAMINED EVERY 10 FEET FROM  
2700 FEET TO A TOTAL DEPTH OF 3161 FEET.

FORMATION TOPS

<u>FORMATION</u> <u>ELEVATION</u>	<u>DEPTH</u>	<u>SUB SEA DEPTH</u>
		1353 K.B.
MISSISSIPPI	2820	-1467
MISSISSIPPI CHERT	2853	-1500
KINDERHOOK SHALE	3107	-1754
HUNTON LIME	3157	-1804
TOTAL DEPTH	3161	-1808

## FORMATIONS OF INTEREST

MISSISSIPPI CHERT 2853 to 2861

CHERT AND DOLOMITIC LIME. LIGHT ODOR AND SHOWS OF  
FREE OIL IN 25% OF SAMPLE. DRILL STEM TEST WAS RUN ON THIS  
ZONE AND RECOVERED 1200 FEET OF SALT WATER.

RECEIVED  
MAR - 9 1981CONSERVATION DIVISION  
Wichita, Kansas