

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 181-20381-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_.

Well Operator: Rosewood Resources, Inc. KCC License #: 33019

Address: 2711 N. Haskell Ave., Suite 2800, LB #22 City: Dallas  
(Owner / Company Name) (Operator's)

State: Texas Zip Code: 75201 Contact Phone: (970) 324 - 1686

Lease: Linin Well #: 1-1M Sec. 1 Twp. 9 S. R. 40  East  West

SE - NW - NW - NW Spot Location / QQQQ County: Sherman

613' Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

613' Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 5 1/2" Set at: 378' Cemented with: 62 Sacks

Production Casing Size: 2 7/8" Set at: 1487' Cemented with: 65 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf 1' @ 1350', 4spf. Perf 1' @ 1000', 4spf

Elevation: 3713' ( G.L. /  K.B.) T.D.: 1500' PBTD: 1499' Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): First we will perforate at 1000', 4spf. Pump 37 sacks and 100lbs of cotton seed hulls in lead cement down 2 7/8" casing. Pump 25 sacks and 50lbs of cotton seed hulls down 5 1/2" surface casing. Cut off casing 5' below ground level.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Tom Roelfs

Phone: (970) 324 - 1686

Address: PO Box 926 City / State: St. Francis, KS 67756

Plugging Contractor: Longhorn Cementing Co. Advanced Drilling KCC License #: 33532  
(Company Name) (Contractor's)

Address: 44963 County Road K, Yuma, Colorado, 80759 Phone: (970) 848 - 0799

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/15/2008 Authorized Operator / Agent: Wayne Mohr  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 19 2008  
CONSERVATION DIVISION  
WICHITA, KS

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

ROSEWOOD RESOURCES, INC.  
2711 N HASKELL STE 2800 LB # 22  
DALLAS, TX 75204

May 20, 2008

Re: LININ #1-1M  
API 15-181-20381-00-00  
1-9S-40W, 613 FNL 613 FWL  
SHERMAN COUNTY, KANSAS


Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after November 16, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,



Steve Bond  
Production Department Supervisor

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550