

JUN 05 2008

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

CONSERVATION DIVISION
WICHITA, KS

API # 15 - 047-20,640-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056

Address: 9431 E. Central, Suite 100, City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481, Ext. 216

Lease: HAWES Well #: 1-2 Sec. 212 Twp. 24-25 S. R. 17 East West

C - NW - NE Spot Location / QQQQ County: Edwards

660 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: NONE Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 304' Cemented with: 225sx Sacks

Production Casing Size: 4-1/2" Set at: 4578' Cemented with: 175sx Sacks

List (ALL) Perforations and Bridgeplug Sets: 4412' - 4418', 4480' - 4488'

Elevation: 2117 (G.L. / K.B.) T.D.: 4580' PBDT: None Anhydrite Depth: 1150'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):
Heavy mud, hulls, cement and plug according to KCC specifications

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Mr. Rob Long Phone: (620) 793 - 0915

Address: 709 E. Santa Fe City / State: Ellinwood, KS. 67526

Plugging Contractor: Quality Well Service KCC License #: 31925

Address: 190 US Highway, Ellinwood, KS. 67526-8911 Phone: (620) 727 - 3409

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6/04/2008 Authorized Operator / Agent: Loveness Mpanje
(Signature)

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- HAWES #1-2
Located: 660' FNL; 650' FWL, NE/4, Section 2-25S-17W,
Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 21, 1980

COMPLETED: March 28, 1980

TOTAL DEPTH: 4580'

LOG

0 - 190 Sand, Clay
s
190 - 2045 Shale
2045 - 3675 Lime and Shale
3675 - 3980 Lime
3980 - 4160 Lime and Shale
4160 - 4525 Lime
4525 - 4580 Lime and Shale

CASING RECORD

Ran 7 joints 8 5/8", 28# casing. 292.22'
set at 304' K.B. Cemented with 225 sacks
60/40 Pozmix with 3% cc. Plug down at
1:45 PM, 3-21-80, by Howco.

Ran 124 joints 4 1/2", K-55, 10.5# casing.
4579.41' set at 4578' G.L. Cemented with
50 sacks Howco Lite, followed with 125
sacks Regular Pozmix with 18% salt, 3/4%
CFR-2, 5# gilsonite per sack, 1/8# tuffiber,
1/8# flocele. Plug down at 3:30 PM,
3-28-80, by Howco.

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 05 2008

CONSERVATION DIVISION
WICHITA, KS

Deviation Surveys: 1 1/2° at 2045'
1° at 4445'

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

June 06, 2008

Re: HAWES #1-2
API 15-047-20640-00-00
2-25S-17W, 660 FNL 1990 FEL
EDWARDS COUNTY, KANSAS


Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after December 3, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,



Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888