

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 185-21,828-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056
(Owner / Company Name) (Operator's)

Address: 9431 E. Central, Suite 100,, City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481, Ext. 216

Lease: SMITH ESTATE "B" Well #: 4-21 Sec. 21 Twp. 21 S. R. 11 East West

- NW - NW - NE Spot Location / QQQQ County: Pratt

330 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2200 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: NONE Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 305' Cemented with: 235sx Sacks

Production Casing Size: 4-1/2" Set at: 3479' Cemented with: 150sx Sacks

List (ALL) Perforations and Bridgeplug Sets: 3408' - 3412'

Elevation: 1748' (G.L. / K.B.) T.D.: 3480' PBDT: 3458' Anhydrite Depth: 475'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): _____

Dump cement and plug according to KCC specifications

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Mr. Rob Long Phone: (620) 793 - 0915

Address: 709 E. Santa Fe City / State: Ellinwood, KS. 67526

Plugging Contractor: Quality Well Service KCC License #: 31925
(Company Name) (Contractor's)

Address: 190 US Highway, Ellinwood, KS. 67526-8911 Phone: (620) 727 - 3409

Proposed Date and Hour of Plugging (if known?): 6/04/2008

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6/04/2008 Authorized Operator / Agent: Loveness Mpanje
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 05 2008
CONSERVATION DIVISION
WICHITA, KS

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - SMITH ESTATE B-4

Located: 330' FNL; 2300' FEL, NE/4, Section 21-21S-11W,
Stafford County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 26, 1983

COMPLETED: August 1, 1983

TOTAL DEPTH: 3480'

LOG

0 - 125 Sand and Clay
125 - 309 Red Shale
309 - 1351 Shale
1351 - 3480 Lime and Shale

CASING RECORD

Ran 7 joints 8 5/8" casing. 293.81'
pipe set at 305' K.B. Cemented with
235 sacks 60/40 Pozmix, 2% gel and 3%
cc. Plug down at 8:30 PM, 7-26-83, by
Howco.

Ran 86 joints 4 1/2", 10.5# casing.
3469.36' pipe set at 3479' K.B.
Cemented with 150 sacks F. G. Holl
Mix. Plug down at 3:45 PM, 8-1-83,
by Howco.

Deviation Surveys: 3/4° at 1668'
2° at 3145'

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 05 2008

CONSERVATION DIVISION
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

HOLL, F.G., COMPANY L.L.C.
9431 E CENTRAL STE 100
WICHITA, KS 67206-2563

June 06, 2008

Re: SMITH ESTATE B #4-21
API 15-185-21828-00-00
21-21S-11W, 330 FNL 2200 FEL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after December 3, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond

Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888