

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

#6 WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-03541-00-00

LEASE NAME Coddington #2

WELL NUMBER _____

SPOT LOCATION NW SW NE

SEC. 34 TWP. 9 RGE. 20w(E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 12/13/84

Plugging Completed 12/13/84

LEASE OPERATOR Dane G. Hansen Trust

ADDRESS Box 187, Logan, Ks. 67646

PHONE # (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3846'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	182'	none
				5 1/2"	3839'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug job only - No pipe recovery. Plugged well with 6 hulls, & 400 sacks 50/50 poz 8% gel down 5 1/2".

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION
01-07-1985
JAN 07 1985

My Commission expires: _____
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1984

Irene Hoover
Notary Public

15-163-03541-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN FARM NAME CODDINGTON #2
 LOCATION NW SW NE Sec. 34-9-20W
 POOL NAME _____ COUNTY Rooks STATE Kansas
 COMMENCEMENT DATE May 27, 1953 COMPLETION DATE June 6, 1953

LOG OF WELL

Elevation: 2289 R.B.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	182	Shale		
182	774	Shale-Shells		
774	792	Sand		
792	855	Shale		
855	1255	Shale-Shells		
1255	1505	Sand	0 - 1500'	
1505	1600	Red Bed-Shale		
1600	1771	Red Bed		
1771	1800	Anhydrite		
1804	2210	Shale-Shells	0 - 2000'	
2210	2400	Lime-Shale		
2400	2518	Lime-Shale	0 - 2500'	
2518	2650	Lime-Shale		
2650	2785	Shale-Lime		
2785	2900	Lime-Shale		
2900	2987	Lime		
2987	3055	Lime-Shale	0 - 3000'	
3055	3175	Lime-Shale		
3175	3261	Lime		
3261	3355	Lime-Shale		
3355	3410	Lime-Shale		
3410	3441	Lime		
3441	3518	Lime-Shale	0 - 3500'	
3518	3562	Lime-Shale		
3562	3597	Lime		
3597	3625	Lime-Shale		DST 3614-3625'
3625	3655	Lime		
3655	3705	Lime		
3705	3754	Lime-Shale		
3754	3805	Lime		
3805	3837	Shale-Lime		
3837	3846	Lime		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 182' of 8 5/8" OD Casing.
 Set 3842.09' of 5 1/2" 14# OD Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

BY D. G. HANSEN FARM NAME CODDINGTON #2
 BY Vicky Jacobs
 C-G DRILLING CO.

Subscribed and sworn to before me this 8th day of June, 1953.

My commission expires: 11/21/55

Marilyn Schmidt
 Notary Public

RECEIVED
 STATE COMMISSION
 OCT 15 1984
 CONSERVATION DIVISION
 Wichita, Kansas

RECEIVED
 JUN 10 1953
 DANE G. BALES