

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-03543-00-00  
API NUMBER drilled 8/53

LEASE NAME Coddington  
WELL NUMBER 4

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3630 Ft. from S Section Line  
330 Ft. from E Section Line

SEC. 34 TWP. 9 RGE. 20 (E) or (W)  
COUNTY Rooks

LEASE OPERATOR The Dane G. Hansen Trust  
ADDRESS P. O. Box 187, Logan, Kansas 67646  
PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Date Well Completed 8/28/53

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 4:45 P.M. 2/18/88

Plugging Completed 6:00 P.M. 2/18/88

The plugging proposal was approved on February 18, 1988 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3824 Bottom 3829 T.D. 3829

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	160.32'	None
				5 1/2"	3828.03'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.  
Down 5 1/2" csg., at 1000# max. pressure, mixed 25 sx cement, then mixed 5 sx hulls w/175 sx cement and shut in at 800#.  
Pressured annulus (8 5/8" csg.) to 800# and shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cement Co., Inc. License No.           

Address Box 31, Russell, Kansas 67665

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Harold Parsons (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Harold Parsons

(Address) Box 353, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 29 day of February, 19 88



Betty Jane Bittel  
Notary Public

My Commission Expires: July 17, 1988

REC'D - 4 1988  
03-04-1988  
CONSOLIDATION DIVISION  
Wichita, Kansas  
Form CP-4  
Revised 07-87

15-163-03543-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen FARM NAME Coddington #4  
LOCATION NE SE NE, Sec. 34-9-20W  
POOL NAME \_\_\_\_\_ COUNTY Rooks STATE Kansas  
COMMENCEMENT DATE August 20, 1953 COMPLETION DATE August 28, 1953

LOG OF WELL

Elevation: 2269' R.B.  
All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	161	Shale-Sand		
161	1225	Shale-Sand		
1225	1467	Sand		
1467	1739	Shale-Shells	0° - 1500'	
1739	1776	Anhydrite		
1776	1825	Shale-Shells		
1825	2315	Lime-Shale	0° - 2000'	
2315	2495	Lime-Shale		
2495	2650	Lime-Shale	0° - 2500'	
2650	2800	Lime-Shale		
2800	2945	Lime-Shale		
2945	3045	Lime-Shale	0° - 3000'	
3045	3225	Lime-Shale		
3225	3335	Lime-Shale		
3335	3435	Lime-Shale		
3435	3490	Lime-Shale		
3490	3535	Lime-Shale	0° - 3500'	
3535	3585	Lime-Shale		
3585	3608	Lime		DST 3608-3596
3608	3640	Lime		
3640	3705	Lime-Shale		
3705	3770	Lime-Shale		
3770	3815	Lime		
3815	3830	Lime		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 160.32' of 8-5/8" Surface Casing.  
Ran 3828.03' (123 Jts) 5-1/2" OD Casing.

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Vicky Jacobs  
Office Manager

Subscribed and sworn to before me this 31st day of August, 1953.

My commission expires: 6/17/57

Barbara Donaldson  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 4 1953  
REGISTRATION DIVISION  
WICHITA, KANSAS