


15-065-00153-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Graham County. Sec. 2 Twp. 9S Rge. (E) 21 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE, SE, SW
Lease Owner Jones, Shelburne & Farmer, Inc.
Lease Name Newell Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 6 19 50
Application for plugging filed December 6 19 50
Application for plugging approved December 6 19 50
Plugging commenced December 6 19 50
Plugging completed December 6 19 50
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production Never Produced 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty
Producing formation Depth to top Bottom Total Depth of Well 3793 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	167'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Hole filled with heavy mud.
- Halliburton plug pushed to 160'.
- One-half sack Hulls dumped onto top of plug.
- Fifteen sacks cement mixed and spotted on top of hulls.
- Second Halliburton plug pushed to 40 feet.
- One-half sack Hulls spotted on top of hulls.
- Ten sacks cement mixed and hole filled to top with same.

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1950
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to JONES, SHELBURNE & FARMER, INC. 12-11-50
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
John O. Farmer (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *John O. Farmer*
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of December, 1950

Phyllis Bethany
Notary Public.

My commission expires June 3, 1953

PLUGGING
FILE SEC 27 9 R 116
BOOK PAGE 47 LINE 40

JONES, SHELBURNE & FARMER, INC.
OKLAHOMA CITY, OKLA.

REMITTANCE STATEMENT N^o 8602

TO State Corporation Commission, Conservation Division, 800 Bitting Bldg., Wichita, Kansas

DATE	ITEMS		NET AMOUNT
12-14-50	Plugging Assessment: No. 1 Newell SE SE SW Sec. 2-9-21W Graham County, Kansas	\$ 25.00	\$ 25.00
15-065-00E3-00-00			

ATTACHED CHECK IS IN PAYMENT OF ACCOUNT STATED ABOVE. DETACH BEFORE DEPOSITING. NO RECEIPT REQUIRED.

STATE OF KANSAS

INVOICE

December 11, 1950¹⁹

To: Jones, Shelburne & Farmer, Inc.

Russell, Kansas

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

For: PLUGGING

ASSESSMENT AS FOLLOWS:

15-065-00153-00-00

Newell Well No. #1
SE SE SW 2-9-21W
Graham County
File No. 47-40

\$25.00

NOTE: No a .

8608

RECEIVED
STATE CORPORATION COMMISSION
12-16⁵⁰ DEC 16 1950
C-77
CONSERVATION DIVISION
Wichita, Kansas

RETURN THIS COPY WITH REMITTANCE



Jones, Shelburne & Farmer, Inc.

Russell, Kansas

15-065-00153-00-00

CONTRACTOR'S VERIFIED LOG

Operator JONES, SHELburne & FARMER, INC. Farm Name NEWELL Well No 1

Location SE, SE, SW SECTION 2-9S-21W

Pool Name _____ County GRAHAM State KANSAS

Commencement Date November 27, 1950 Completion Date December 6, 1950

Log of Well

Depth		Formation	Deviation from vertical (degrees)	Remarks
From	To			
●	167	Shale		
167	865	Shale and Shells		
865	1450	Shale and Sand		
1450	1655	Shale and Shells		
1655	1695	Anhydrite		
1695	2100	Shale and Shells		
2100	3435	Lime and Shale		
3435	3585	Lime		
3585	3770	Lime and Shale		
3770	3793	Lime		
	3793	Total Depth		
		TOPS		
	2158	Elevation		
	1655	Anhydrite		
	3135	Topeka		
	3346	Heebner		
	3386	Lansing		
	3746	Arbuckle		
		Ran Schlumberger Log		

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 11 1950
 CONSERVATION DIVISION
 Wichita, Kansas

12-11-50

PLUGGING

FILE SEC 2 T 9 R 21W

BOOK PAGE 47 LINE 40

Depth		Formation	Deviation from vertical (degrees)	Remarks
From	To			
3110	3113	3110-3113		
3113	3116	3113-3116		
3116	3119	3116-3119		
3119	3122	3119-3122		
3122	3125	3122-3125		
3125	3128	3125-3128		
3128	3131	3128-3131		
3131	3134	3131-3134		
3134	3137	3134-3137		
3137	3140	3137-3140		
3140	3143	3140-3143		
3143	3146	3143-3146		
3146	3149	3146-3149		
3149	3152	3149-3152		
3152	3155	3152-3155		
3155	3158	3155-3158		
3158	3161	3158-3161		
3161	3164	3161-3164		
3164	3167	3164-3167		
3167	3170	3167-3170		
3170	3173	3170-3173		
3173	3176	3173-3176		
3176	3179	3176-3179		
3179	3182	3179-3182		
3182	3185	3182-3185		
3185	3188	3185-3188		
3188	3191	3188-3191		
3191	3194	3191-3194		
3194	3197	3194-3197		
3197	3200	3197-3200		
			Total Depth	

Was Well to be deepened by another Contractor? Yes No

CASING LEFT IN HOLE AFTER COMPLETION OR ABANDONMENT

Size	Wt.	Grade	Range	Thread	SNG	FOOTAGE					
						Delivered	Run	Set At	Unused	Pulled	Left in Hole
8 5/8"		Cemented with 100 sacks				167'				None	167'

Deviation From Vertical Data Is Correct as Shown

Company Superintendent _____

(This space for Company use)

The foregoing Well Log and other data are correct.

JONES, SHELBURNE & FARMER, Inc.
Contractor.

By *John W. Farmer*