


15-065-00330-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 5 Twp. 9 Rge. (E) 21 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SW  
Lease Owner PEEL HARDMAN - APPLEMAN - VEEDER SUPPLY CO.  
Lease Name Miller Well No. 1  
Office Address Box 359, Hoisington, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 10, 19 52  
Application for plugging filed January 10, 19 52  
Application for plugging approved January 10, 19 52  
Plugging commenced January 10, 19 52  
Plugging completed January 10, 19 52  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3882' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	220'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from 3882 to 210' plug at 210' with 1/2 sack of hulls and 15 sacks of cement. Mud from 165' to 40' plug at 40' with 1/2 sack of hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Veeder Supply & Development Co. 1-22-52  
Address P. O. Box 201  
Cherryvale, Kansas

STATE OF KANSAS, COUNTY OF MONTGOMERY, ss.

FLOYD W. HILD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. THE VEEDER SUPPLY & DEVELOPMENT COMPANY

(Signature) Floyd W. Hild

P.O. Box 201, Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18th day of January, 1952

My commission expires July 11, 1952 Notary Public.




PLUGGING  
FILE SEC 51-9-R-216  
BOOK PAGE 138 LINE 3

15-065-00330-00'00

Company **Appleman - Peel Hardman - Veeder Supply Co.**  
 Farm **Miller** No. **1**

Sec. **5 T. 9S R. 21W**  
 Loc. **C. SE SE**  
 County **Graham County, Kansas**



Total Depth **3882'**  
 Comm. **12-27-51** Comp. **1-10-52**  
 Shot or Treated  
 Contractor **Veeder Supply Co.** Drilled with Rig - **D.**  
 Issued No. of Days - **15**  
 No. of Bitts -

Casing  
 20 in. 10 in.  
 15 1/2 8 1/4  
 12 1/2 6 5/8 Run 220' of 8-5/8" Casing Cemented with 125 sacks cement.  
 13 3/8 5 3/16  
 Elevation  
 Production

Figures Indicate Bottom of Formation

Clay	0	20	20
Rock	20	35	15
Sand	35	60	25
Shale Sand	60	135	75
Shale	135	420	285
Shale Shells	420	780	360
Shale	780	950	170
Sand Shale	950	1000	50
Sand	1000	1070	70
Shale Shells	1070	1140	70
Shale Iron Sand	1140	1320	180
Sand	1320	1520	200
Shale Red Bed	1520	1784	264
Anhydrite	1784	1816	32
Shale Shells	1816	2135	319
Salt Shale	2135	2230	95
Shale Lime	2230	2450	220
Lime	2450	2500	50
Lime Shale	2500	2510	10
Shale Lime Iron	2510	2610	100
Lime Shale	2610	2920	310
Lime	2920	2945	25
Lime Shale	2945	3150	205
Lime	3150	3238	88
Lime Shale	3238	3290	52
Lime	3290	3360	70
Lime Shale	3360	3430	70
Lime	3430	3695	265
Lime Shale	3695	3805	110
Shale Chert	3805	3840	35
Lime Shale Chert	3840	3882	42
Total Depth	3882'		

Plugged at 210 feet with 15 sacks cement  
 Plugged at 40 feet with 10 sacks cement

**RECEIVED**  
 STATE COMMISSION  
 JAN 22 1952  
 CONSTRUCTION DIVISION  
 Wichita, Kansas  
 1-22-52

**PLUGGING**  
 FILE SEC 5 T 9 R 20  
 BOOK PAGE 131 LINE 3